




PAVILION DETAILS	
LAND USE	COMMERCIAL
BUILDING TYPOLOGY	RENTED PAVILION
EXHIBIT AREA M2	436.56 sq.m
OFFICE AREA M2	382.57 sq.m
GROUND FLOOR CLEARANCE HEIGHT (SLAB TO CEILING)	5.00 m (Including a 1m MEP zone)
FIRST FLOOR CLEARANCE HEIGHT (SLAB TO CEILING)	3.46 m (Not including 150 mm for floor build up)

DESIGN NOTES
1. REFER TO 'RENTED PAVILION GUIDE' WHERE APPROPRIATE FOR DESIGN GUIDES & CONTROLS
2. THIS PAVILION SHEET IS SUBJECT TO CHANGE.
3. INFRASTRUCTURE ALLOCATION IS BASED ON DM GFA DEFINITION.
4. PARTICIPANTS SHOULD ABIDE BY DUBAI MUNICIPALITY AND DUBAI SOUTH CODES AND OTHER AUTHORITIES AS NOTED IN THE GUIDELINES.
5. THE PARTICIPANT IS RESPONSIBLE TO DESIGN AND IMPLEMENT AN EFFECTIVE CONSTRUCTION STRATEGY TO AVOID ANY IMPACT OR DAMAGES TO STRUCTURE OF EXTERNAL SPACES.
6. NO LPG PROVISIONS ARE AVAILABLE WITHIN THE PAVILION PREMISES.
7. NO KITCHEN EXTRACT IS PROVIDED.
8. THE MAXIMUM ALLOWED COMMERCIAL AREA PER PAVILION IS 20 PERCENT OF THE GROUND FLOOR AREA OF THE PAVILION.
9. ANY CHANGES TO INSTALL FOOD AND BEVERAGE PROVISIONS MUST NOT AFFECT THE STRUCTURAL INTEGRITY OF THE PAVILION AND MUST BE APPROVED BY THE ORGANISER AND AUTHORITIES.
10. PARTICIPANTS MUST RETURN THEIR PAVILION TO THE ORGANISER IN THE SAME CONDITION AS IT WAS RECEIVED.

STRUCTURAL LOADS			
LIVE LOAD	5 kN/m2	SUPERIMPOSED DEAD LOAD	5 kN/m2

INFRASTRUCTURE NOTES	
Potable Water	32mm PPR provision with connected flow rate of 0.32 l/s, max flow rate available 0.41 l/s
LPG	None available at present
Outside Air Provision	Ground: 1.01m3/s First: 0.21m3/s
Electricity	1No. 3-phase SMDB provided at ground floor. Total connected load is 89.85kW Spare Capacity is 17.10kW
Safety & IT	Landlords: 1No. Rack for IT 1No. Rack for Safety CCTV cameras and access control provided as per the layouts
Back-up Power	None for tenant
Cooling	Ground: 92kW First: 42kW
Fire Protection	Sprinklers & Hose Reels
Fire Alarm	Dedicated fire alarm panel connected to the organisers network.
Telecommunications	2-core fibre connection from telecoms room to optical network unit at ground floor.



COUNTRY	PLOT CODE	PLOT SHEET NUMBER	DATE	 EXPO 2020 إكسبو ٢٠٢٠ دبي، الإمارات العربية المتحدة DUBAI UNITED ARAB EMIRATES
REPUBLIC OF CROATIA	EXPO 2020 DUBAI - PAVILION : MSR	05007-PLP-IPA0035655-AR-000001	OCT - 2018	
	WBS : 600		REVISION 2	